

**Kirkbymoorside Town Council  
Manor Vale Management Committee  
Price for Tree Work in Manor Vale  
November 2012**

**Name & address of tenderer:**

**Tel no:**

**E-mail:**

**Schedule of work to be carried out**

<b>Tree No</b>	<b>Type</b>	<b>Work Required</b>	<b>Price excl VAT</b>
705 (Yellow spot)	Oak	Reduce crown to c 15m to ensure if it falls it will be a safe distance from the road	
706 (White spot)	Oak	Clean crown of deadwood over footpath up to 12m	
709 (Yellow spot)	Ash	Remove secondary branch to east.	
710 (Yellow)	Ash	Reduce to 10-12m	
716 (white)	Oak	Remove deadwood over path only. Shorten branch to south by c 3m to leave woodpecker hole.	
717 (white)	Oak	Remove dead wood over path up to 12m.	
718 (white)	Oak	Remove dead wood over path.	
719 (white)	Oak	Remove central dead branch and other dead wood over path	
721 (yellow)	Oak	Fell at ground level	
723 (white)	Oak	Remove dead wood from over path	
724 (yellow)	Oak	Reduce tree to 9m	
731 (yellow)	Ash	Reduce to 6-8m if possible or fell to near ground level. Please specify which option selected and why.	
734 (white)	Ash	Reduce NE section to ensure does not fall over path	
735 (yellow)	Ash	Fell to 4-5m to leave as wildlife resource	
737 (yellow)	Ash	Reduce by 50%	
		Total Price excl VAT	

**Other Information**

**Signed**

**Date**