

Your ref:

Our ref: Kirkbymoorside 2017/P2

Contact: Peter Ball – Road Lighting

Tel: 01609 532896

Peter Ball

NYCC 41 Northallerton Road Leeming Bar North Yorkshire DL7 9AL

E-mail: peter.ball@northyorks.gov.uk

20 November 2017

Lisa Bolland, clerk to Kirkbymoorside Town Council

Re: Phase 2, replacement of last remaining concrete column and all the obsolete mercury MBFU lanterns

The estimate to carry out phase 2 (24 town lights) is £15,890 + VAT.

This work includes the following:-

Replacing the last remaining concrete column (Castlegate, col LP 2) with a 6m lizard grey steel column complete with a 10W LED lantern, and

Replacing all the obsolete mercury MBFU lanterns with either 10W or 20W LED lanterns, depending on location. This will also include replacing most of the sub-standard pole/ wall mounted electrical junction box which will necessitate involving Northern Powergrid (NPG) to transfer their power supply cables.

The only problems that we may encounter are invariably the wall mounted light units. Crown Square, LP 4; Manor Close, LP 1; Sunnyside, LP 1; Tinley Garth LP 4. These locations will require permission from the building/ property owner to go ahead and carry out the necessary work to upgrade the lighting.

If there is anything you wish to discuss, please do not hesitate to contact me.

Kind Regards,

Project Manager (Parish Lighting) Mr P. Ball