LEGEND

- **Existing Trees & Hedgerows to be Retained**
- **Existing Trees & Hedgerows to be Removed**
- **Proposed Spine Road Trees**
  Trees to be planted as 40-45cm girth, Semi-Mature, 6-8m high with 2.5m clear stem. Trees to be secured with underground guying system.
- **Proposed Individual POS Native Trees**
  Trees to be planted as 20-25cm, Semi-mature, 4.5-6m high with 2m clear stem. Trees to be secured with underground guying system.
- **Proposed Medium Size Ornamental Trees**
  Trees to be planted as 14-16cm girth, Extra Heavy Standard, 3.5-4m high. Trees to be staked and secured with suitable rubber ties.
- **Proposed Small Ornamental Trees**
  Trees to be planted as 10-12cm girth or 50L containers, 2-3m high and secured with single stake and suitable rubber ties.
- **Proposed Hedgerows**
  Evergreen hedgerows to be planted in 10L containers at a rate of 3-4 per lin. metre.
- **Proposed Native Hedgerow**
  Native hedgerows to be planted as a double staggered row at 300mm centres, 80-100cm bareroot stock, fitted with spiral guards or similar
- **Proposed Shrub Planting**
  Ornamental shrub planting, to be planted in 3-4L containers at 3-4 p/m², and enhanced by feature specimens in 10-20L pots.
- **Proposed Native Shrub Mix**
  To be planted as bareroot stock, 60-80cm, at 2 p/m², and protect with spiral guards
- **Proposed Woodland Edge Mix**
  Mix of native shrubs and trees planted at 1,5m centre.
  Size: 20-30cm/ 2L pots
- **Proposed Native woodland Mix**
  Mix of Native Trees planted at 2m centre
  Size: 40-60cm
- **Proposed Wildflower For Wetland**
  To be Emorsgate EM8 Meadow mixture for Wetlands, supplied by Emorsgate or similar approved. Including 80% of ornamental grasses and 20% of wildflowers. Sowing rate 4/gm2.
- **Proposed Wildflower Meadow**
  To be Emorsgate EM2 Standard General Purpose Meadow Mix, supplied by Emorsgate or similar approved. Including 80% of ornamental grasses and 20% of wildflowers. Sowing rate 4/gm2.
- **Proposed Amenity Grass**
  Front gardens to be turfed.
  Back gardens to client specification.
- **Proposed Amenity Grass**
- **Proposed Bulbs**
- **Proposed Footpath**
- **Play Area**
  LEAP/NEAP

TYPICAL SPECIES LIST

Avenue Trees (within Highways)
40-45cm girth 6-8m high, Semi Mature with 2m clear stem;

Acer platanoides 'Deborah'
Liquidambar styraciflua
Pyrus 'Chanticleer'
Liriodendron 'Fastiagata'
Quercus robur 'Fastiagata'
Carpinus betulus 'Frans Fontaine'
Prunus padus 'Watereri'

Trees within Public Open Space
20-25/ 14-16cm girth, 4-6m high, Semi-mature/ Extra Heavy Standard;

Amelanchier lamarckii
Betula nigra
Fagus sylvatica
Liriodendron tulipifera
Prunus Padus 'Watereri'
Quercus palustris
Quercus robur

Native Trees
Acer campeste
Betula pendula
Carpinus betulus
Fagus sylvatica
Malus sylvestris
Prunus avium
Quercus robur

Hedge Planting
Planted in 10L containers
Eleagnus ebbingei
Griselinia littoralis
Prunus laurocerasus 'Rotundifolia'
Osmanthus burkwoodii
Photinia 'Red Robin'

Shrub Planting
Planted as 3-5L pots at 3-4 per sq.m;

Cornus alba 'Sibirica
Cotinus Coggygria 'Royal Purple'
Escallonia 'Donard Star'
Hydrangea 'Anabelle'
Hebe 'Autumn Glory'
Lavandula varieties
Brachysglottis
Fuschia 'Mrs Popple'
Ilex crenata
Pieris japonica
Choysia ternata
Euonymus 'Emerald n Gold'
Geranium 'Wargrave Pink'
Nandina domestica 'Obsessed'
Prunus 'Otto Luyken'
Rosmarinus 'Mrs Jessops Upright'
Sarcococca humulis
Skimmia japonica 'Kew Green'
Spirea nipponica 'Snowmound'
Viburnum davidii

Woodland Planting
40-60cm girth, 2m centres
Acer Campestre
Betula Pendula
Quercus Robur
Tilia Cordata
Sorbus Aucuparia

Woodland Edge Mix
Planted in 2L container
or 20-30cm girth, 1,5m centres
Crataegus Monogyna
Prunus Spinosa
Viburnum Opulus
Rosa Canina
Ligustrum Vulgare

GENERAL NOTES

1. This drawing is the copyright of tpm landscape Ltd and cannot be reproduced in any form without the consent of the company.
2. This drawing is to be read in conjunction with detail landscape drawings, details and specification.
3. This drawing is to be read in conjunction with all relevant Architects', Engineer's, Specialists, Bills of Quantities and Specifications.
4. The insertion of any firm or proprietary brand on this drawing is an indication of the class or quality required and does not exclude the use of alternative materials that are equal in performance, quality and appearance, provided that they have been approved in writing by the Landscape Architect.
5. The Contractor is responsible for accurately ascertaining the position of underground services and responding to all relevant service easement requirements.
6. All dimensions are in millimetres unless stated otherwise, for the purposes of construction this drawing must not be scaled and only written dimensions used. Written and scaled dimensions to be checked on site, any discrepancies reported prior to work commencing. IF IN DOUBT PLEASE ASK.
7. All work and materials are to be in accordance with the relevant British Standards and Code of Practice.
8. All Proprietary products are to be used strictly in accordance with the manufacturer's instructions and details.

REVISION NOTES

Rev	By	Description	Date
B	DC	Updates in line with client comments.	12.12.19
A	GJC	Updates in line with comments.	11.12.19

Client
Countryside Properties

Project
Kirkbymoorside

Description
Landscape Masterplan

Status
For Approval

Scale @ A1	Drawn	Checked	Date
1:1000	DC	DC	28.11.19
Job number	**Drawing number**		**Revision**
3534	101		B

N

tpm landscape
chartered landscape architects
address: 4th Floor Studio 10 Little Lever St Manchester M1 1HR
tel: 0161 235 0600 fax 0601 email info@tpmlandscape.co.uk

TYPICAL TREE PLANTING

Carpinus betulus 'Frans Fontaine'

Quercus robur 'Fastigiate Koster'

Liriodendron 'Fastiagata'

Betula pendula

TYPICAL HEDGE PLANTING

Prunus laurocerasus 'Rotundifolia'

Osmanthus burkwoodii

Eleagnus x ebbingei

Griselinia littoralis

TYPICAL SHRUB PLANTING

Spiraea varieties

Nandina domestica 'Firepower'


Pittosporum varieties

Hebe varieties

Lavender varieties

Skimmia varieties